BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT40942

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/28/2019-20, Date: 17.03.2020

Name of Work: Improvements to Storm water Drains in ward no 5 Jakkur

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of H A MADHU GOWDA ( )	
				In Figures	In Words
1	216.12	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. MORTH/ Chapter 3 complete as per specifications and directions of the Engineer in charge.	Cum	182.68	Rupees One Hundred Eighty Two and Sixty Eight Paise Only
2	23.16	KSRB 4-1.2 : Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2	Cum	4844.96	Rupees Four Thousand Eight Hundred Forty Four and Ninety Six Paise Only
3	62.98	Providing laying plain/ reinforced cement concrete for side Drains Using M20 nominal mix Concrete with OPC at 300kgs.With 20mm and Down size granite metal coarse aggregate at 0.69cum and fine aggregate at 0.43cum Machne mixed, well compacted for wall and Bottom including centering shuttering,cost of materials,HOM of Machinery,Curing Etc.,Complete Excluding cost of Steel as per morth MORTH specification No. 1500, 1700, 2200. Including Cost of material, Labour, HOM complete as per Specification-WALL & Bottom thickness 15Cm(Item No 37.59.2 page no 271)	Cum	6221.77	Rupees Six Thousand Two Hundred Twenty One and Seventy Seven Paise Only
4	3.78	KSRB M2200-6 Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. MORTH Specification NO.1600&2200Specification No. Pg No.229 Item No.28.8.2	Tonne	63647.74	Rupees Sixty Three Thousand Six Hundred Forty Seven and Seventy Four Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
01/09

01/09